


APPLICATION NOTE

Testing bushing CTs in a high noise substation

Objective: This application note demonstrates how to hook up leads and perform the test with MRCT test equipment on bushings CTs of an auto transformer in a high voltage substation with extreme noise and interference.

Test object: Single phase auto transformer




Single phase auto transformer with bushing CTs

Test Equipment: MRCT

H1

Test connections:

Ground the H1 bushing and leave it grounded for the whole duration of testing all CTs as shown below:



Grounding the high side bushing

APPLICATION NOTE

Testing bushing CTs in a high noise substation

Grounding is performed to reduce any induced voltage from overhead energized lines


Testing CTs on H side bushing

MRCT unit has H and X test leads

a) Connection of H leads

Make following connections for H1 and H2 test leads

Bushing	H1	X1	H0-X0	Y1	Y2
MRCT leads	H1	Floating	H2	Grounded	Grounded




b) Connection of X leads

Connect MRCT secondary leads marked X1S, X1, X2, X3, X4, X5 and X5S to the secondary of the CT under test as per the diagram shown below.

APPLICATION NOTE


Testing bushing CTs in a high noise substation



Before proceeding to start the test, please make sure that communication button at the top left side of the software screen is green. This indicates that software is communicating with the test box.



From home screen of the MRCT software select Run All Tests



In the Test selection screen, check all saturation, all ratio and all winding resistance test. Ratio test includes polarity test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation

# Taps 5	Saturation Test	Ratio Test	Winding Resistance	Insulation Resistance
X1-X2	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Secondary <input type="checkbox"/> 1KV
X1-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Ground <input type="checkbox"/> 1KV
X1-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Secondary To Ground <input type="checkbox"/> 1KV
X1-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="button" value="All Ranges"/>
X2-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X4-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	

Saturation/Ratio X1 to Xn Only

All Saturation Tests

All Ratio Tests

All Winding Tests

Concurrent


It is important to **NOT** check insulation resistance test as high side is intentionally shorted to ground to eliminate the interference. User would have to perform the insulation resistance separately.

Hit the play button to run the test

Following diagram will show up. Hit the play button again to confirm and unit will initiate the test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation



The tests will be performed in following order:

- DC winding resistance of CT secondary
- Demagnetization
- Saturation or Excitation Test
- Ratio and Polarity test

At the end of the test, a report similar to below will show up:

APPLICATION NOTE

Testing bushing CTs in a high noise substation

NAMEPLATE DATA CT: CT1X


MANUFACTURER _____ SERIAL NO. 5226t3a001 PHASE _____

ASSET ID _____ ACCURACY CLASS _____ SATURATION STD ANSI 45


BURDEN _____ VA _____

Secondary Voltage Injection

Tap	X1-X2	X1-X3	X1-X4	X1-X5	X2-X3	X2-X4	X2-X5	X3-X4	X3-X5	X4-X5	
R A T I O	Nameplate	1000:5	2200:5	2500:5	3000:5	1200:5	1500:5	2000:5	300:5	800:5	500:5
	Measured	1000.291:5	2200.464:5	2500.626:5	3000.644:5	1200.172:5	1500.335:5	2000.353:5	300.163:5	800.18:5	500.018:5
	% Error	0.029	0.021	0.025	0.021	0.014	0.022	0.018	0.054	0.023	0.004
	Test V (V)	99.866	219.68	249.65	299.57	119.82	149.79	199.71	29.967	79.888	49.920
	Test I (A)	0.1674	0.0761	0.0670	0.0558	0.1395	0.1116	0.0837	0.5579	0.2093	0.3349
	Prim V (V)	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992
	Phase Dev.	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'
	Polarity	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct
Knee	Volt.(V)	196.23	431.30	490.20	589.27	235.07	293.96	393.05	58.893	157.93	99.016
	Cur.(A)	0.2643	0.1203	0.1058	0.0882	0.2209	0.1765	0.1324	0.8801	0.3306	0.5292



Hit the save button to save the file by giving it a file name.



Testing CTs on X1 bushing

Before testing X1 bushing, follow the below steps to enable a specific setting in MRCT software:

Click on the nameplate icon on the home screen of the software as shown below:

APPLICATION NOTE

Testing bushing CTs in a high noise substation



In the nameplate screen, click on the area shown in the blue circle:

This will pop up a window asking to enter a password. Enter password **vapower** (case sensitive)


Hit green OK button

This will enable a new selection check box on nameplate screen: "H2 connected to shroud" as shown below:

APPLICATION NOTE

Testing bushing CTs in a high noise substation

Please note that user does not have to perform these steps every time. It is performed just one time and can be saved as default settings by following the steps below:




MRCT unit has H and X test leads

- a) Connection of H leads
Make following connections for H1 and H2 test leads

Bushing	H1	X1	H0- Xo	Y1	Y2
MRCT leads	H1	H2	Floating	Grounded	Grounded

APPLICATION NOTE

Testing bushing CTs in a high noise substation



Please note that by connecting H1 and H2 test leads as shown above will generate incorrect polarity but that will be taken care of in section below.

In the nameplate screen check the box "H2 connected to Shroud"




This will take care of incorrect polarity issue.

b) Connection of X leads


Connect MRCT secondary leads marked X1S, X1, X2, X3, X4, X5 and X5S to the secondary of the CT under test as per the diagram shown below.

APPLICATION NOTE

Testing bushing CTs in a high noise substation



From home screen of the MRCT software select Run All Tests



In the Test selection screen, check all saturation, all ratio and all winding resistance test. Ratio test includes polarity test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation

# Taps 5	Saturation Test	Ratio Test	Winding Resistance	Insulation Resistance
X1-X2	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Secondary <input type="checkbox"/> 1KV
X1-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Ground <input type="checkbox"/> 1KV
X1-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Secondary To Ground <input type="checkbox"/> 1KV
X1-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="button" value="All Ranges"/>
X2-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X4-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	

Saturation/Ratio X1 to Xn Only

All Saturation Tests

All Ratio Tests

All Winding Tests

Concurrent


It is important to **NOT** check insulation resistance test as high side is intentionally shorted to ground to eliminate the interference. User would have to perform the insulation resistance separately.

Hit the play button to run the test

Following diagram will show up. Hit the play button again to confirm and unit will initiate the test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation



The tests will be performed in following order:

- DC winding resistance of CT secondary
- Demagnetization
- Saturation or Excitation Test
- Ratio and Polarity test

At the end of the test, a report similar to below will show up:

APPLICATION NOTE

Testing bushing CTs in a high noise substation

NAMEPLATE DATA _____ CT: CT1X _____


MANUFACTURER _____ SERIAL NO. 5226t3a001 _____ PHASE _____

ASSET ID _____ ACCURACY CLASS _____ SATURATION STD ANSI 45 _____


BURDEN _____ VA _____

Secondary Voltage Injection

Tap	X1-X2	X1-X3	X1-X4	X1-X5	X2-X3	X2-X4	X2-X5	X3-X4	X3-X5	X4-X5	
R A T I O	Nameplate	1000:5	2200:5	2500:5	3000:5	1200:5	1500:5	2000:5	300:5	800:5	500:5
	Measured	1000.291:5	2200.464:5	2500.626:5	3000.644:5	1200.172:5	1500.335:5	2000.353:5	300.163:5	800.18:5	500.018:5
	% Error	0.029	0.021	0.025	0.021	0.014	0.022	0.018	0.054	0.023	0.004
	Test V (V)	99.866	219.68	249.65	299.57	119.82	149.79	199.71	29.967	79.888	49.920
	Test I (A)	0.1674	0.0761	0.0670	0.0558	0.1395	0.1116	0.0837	0.5579	0.2093	0.3349
Prim V (V)	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	
Phase Dev.	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	
Polarity	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct	
Knee	Volt.(V)	196.23	431.30	490.20	589.27	235.07	293.96	393.05	58.893	157.93	99.016
	Cur.(A)	0.2643	0.1203	0.1058	0.0882	0.2209	0.1765	0.1324	0.8801	0.3306	0.5292



Hit the save button to save the file by giving it a file name.



Testing CTs on X0 bushing

MRCT unit has H and X test leads

- a) Connection of H leads


APPLICATION NOTE

Testing bushing CTs in a high noise substation

Make following connections for H1 and H2 test leads

Bushing	H1	X1	H0- Xo	Y1	Y2
MRCT leads	H1	Grounded	H2	Grounded	Grounded

Please note that by connecting H1 and H2 test leads as shown above will generate incorrect polarity but that will be taken care of in section below.



In the nameplate screen check the box "H2 connected to Shroud"




This will take care of incorrect polarity issue.

b) Connection of X leads


Connect MRCT secondary leads marked X1S, X1, X2, X3, X4, X5 and X5S to the secondary of the CT under test as per the diagram shown below.

APPLICATION NOTE

Testing bushing CTs in a high noise substation



From home screen of the MRCT software select Run All Tests



In the Test selection screen, check all saturation, all ratio and all winding resistance test. Ratio test includes polarity test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation

# Taps 5	Saturation Test	Ratio Test	Winding Resistance	Insulation Resistance
X1-X2	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Secondary <input type="checkbox"/> 1KV
X1-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Ground <input type="checkbox"/> 1KV
X1-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Secondary To Ground <input type="checkbox"/> 1KV
X1-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="button" value="All Ranges"/>
X2-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X4-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	

Saturation/Ratio X1 to Xn Only

All Saturation Tests

All Ratio Tests

All Winding Tests

Concurrent


It is important to **NOT** check insulation resistance test as high side is intentionally shorted to ground to eliminate the interference. User would have to perform the insulation resistance separately.

Hit the play button to run the test

Following diagram will show up. Hit the play button again to confirm and unit will initiate the test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation




The tests will be performed in following order:

- DC winding resistance of CT secondary
- Demagnetization
- Saturation or Excitation Test
- Ratio and Polarity test


At the end of the test, a report similar to below will show up:

APPLICATION NOTE

Testing bushing CTs in a high noise substation



Hit the save button to save the file by giving it a file name.



Testing CTs on Y1 bushing

If the tertiary winding has only single tap, user can change the no. of taps to two by going to nameplate screen:

APPLICATION NOTE

Testing bushing CTs in a high noise substation

Nameplate

No. of CTs No. of Cores **No. of Taps** CT Label Name

Manufacturer

Serial No.

Asset ID

Phase

Accuracy Class

VA

Burden

Meter Protection

H2 Connected to Shroud


Buried CT in Delta Connection

MRCT unit has H and X test leads

- a) Connection of H leads

Make following connections for H1 and H2 test leads

Bushing	H1	X1	H0- Xo	Y1	Y2
MRCT leads	Grounded	Grounded	Grounded	H1 and Grounded	H2




APPLICATION NOTE


Testing bushing CTs in a high noise substation

b) Connection of X leads

Connect MRCT secondary leads marked X1S, X1, X2, X3, X4, X5 and X5S to the secondary of the CT under test as per the diagram shown below.



From home screen of the MRCT software select Run All Tests



In the Test selection screen, check all saturation, all ratio and all winding resistance test. Ratio test includes polarity test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation

# Taps 5	Saturation Test	Ratio Test	Winding Resistance	Insulation Resistance
X1-X2	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Secondary <input type="checkbox"/> 1KV
X1-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Ground <input type="checkbox"/> 1KV
X1-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Secondary To Ground <input type="checkbox"/> 1KV
X1-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="button" value="All Ranges"/>
X2-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X4-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	

Saturation/Ratio
X1 to Xn Only

All Saturation
Tests

All Ratio
Tests

All Winding
Tests

Concurrent


It is important to **NOT** check insulation resistance test as high side is intentionally shorted to ground to eliminate the interference. User would have to perform the insulation resistance separately.

Hit the play button to run the test

Following diagram will show up. Hit the play button again to confirm and unit will initiate the test.

APPLICATION NOTE

Testing bushing CTs in a high noise substation



The tests will be performed in following order:

- DC winding resistance of CT secondary
- Demagnetization
- Saturation or Excitation Test
- Ratio and Polarity test

At the end of the test, a report similar to below will show up:

NAMEPLATE DATA CT: CT1X


MANUFACTURER: _____ SERIAL NO.: 522613a001 PHASE: _____

ASSET ID: _____ ACCURACY CLASS: _____ SATURATION STD: ANSI 45

BURDEN: _____ VA: _____

Secondary Voltage Injection


Tap	X1-X2	X1-X3	X1-X4	X1-X5	X2-X3	X2-X4	X2-X5	X3-X4	X3-X5	X4-X5
Nameplate	1000.5	2200.5	2500.5	3000.5	1200.5	1500.5	2000.5	300.5	800.5	500.5
Measured	1000.291.5	2200.464.5	2500.628.5	3000.644.5	1200.172.5	1500.335.5	2000.353.5	300.163.5	800.18.5	500.018.5
% Error	0.029	0.021	0.025	0.021	0.014	0.022	0.018	0.054	0.023	0.004
Test V (V)	99.866	219.68	249.65	299.57	119.82	149.79	199.71	29.967	79.868	49.920
Test I (A)	0.1674	0.0761	0.0670	0.0558	0.1395	0.1116	0.0837	0.5579	0.2093	0.3349
Prim V (V)	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992	0.4992
Phase Dev.	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'	0°26'
Polarity	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct	Correct
Knee Volt (V)	196.23	431.30	490.20	589.27	235.07	293.96	393.05	58.893	157.93	99.016
Knee Cur (A)	0.2643	0.1203	0.1058	0.0882	0.2209	0.1765	0.1324	0.8801	0.3306	0.5292



APPLICATION NOTE

Testing bushing CTs in a high noise substation

Hit the save button to save the file by giving it a file name.



Testing CTs on Y2 bushing

If the tertiary winding has only single tap, you can change the no. of taps to 2 by going to nameplate screen:

Nameplate

No. of CTs: 1 No. of Cores: 1 **No. of Taps: 2** CT Label: X Name: CT1

Manufacturer: _____

Serial No.: _____

Asset ID: _____

Phase: _____

Meter: _____ Protection: _____

Accuracy Class: _____

VA: _____

Burden: _____

H2 Connected to Shroud: Buried CT in Delta Connection:

MRCT unit has H and X test leads


- a) Connection of H leads

Make following connections for H1 and H2 test leads

Bushing	H1	X1	H0- Xo	Y1	Y2
MRCT leads	Grounded	Grounded	Grounded	H2	H1 and Grounded


APPLICATION NOTE

Testing bushing CTs in a high noise substation



b) Connection of X leads


Connect MRCT secondary leads marked X1S, X1, X2, X3, X4, X5 and X5S to the secondary of the CT under test as per the diagram shown below.



APPLICATION NOTE

Testing bushing CTs in a high noise substation

From home screen of the MRCT software select Run All Tests



In the Test selection screen, check all saturation, all ratio and all winding resistance test. Ratio test includes polarity test.

# Taps 5	Saturation Test	Ratio Test	Winding Resistance	Insulation Resistance
X1-X2	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Primary To Secondary <input type="checkbox"/> 1KV Primary To Ground <input type="checkbox"/> 1KV Secondary To Ground <input type="checkbox"/> 1KV <input type="button" value="All Ranges"/>
X1-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X1-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X1-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X3	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X2-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X4	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X3-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
X4-X5	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	

Saturation/Ratio
X1 to Xn Only

All Saturation
Tests

All Ratio
Tests

All Winding
Tests

▶


It is important to **NOT** check insulation resistance test as high side is intentionally shorted to ground to eliminate the interference. User would have to perform the insulation resistance separately.

APPLICATION NOTE

Testing bushing CTs in a high noise substation

Hit the play button to run the test

Following diagram will show up. Hit the play button again to confirm and unit will initiate the test.




The tests will be performed in following order:

- DC winding resistance of CT secondary
- Demagnetization
- Saturation or Excitation Test
- Ratio and Polarity test

At the end of the test, a report similar to below will show up:

APPLICATION NOTE

Testing bushing CTs in a high noise substation



Hit the save button to save the file by giving it a file name.

